

RS Means Cost Data				
Item	Unit	Notes:	2018 Cost	2018 Cost Index (0.885)
7" Residential Concrete	Square Yard	Hand formed & placed	\$38.00	\$33.63
8" Residential Concrete	Square Yard	Hand formed & placed	\$42.00	\$37.17
9" Residential Concrete	Square Yard	Hand formed & placed	\$47.50	\$42.04
7" Residential Concrete	Square Yard	Slip formed	\$34.50	\$30.53
8" Residential Concrete	Square Yard	Slip formed	\$39.50	\$34.96
9" Residential Concrete	Square Yard	Slip formed	\$44.50	\$39.38
10" Commercial Concrete	Square Yard	Hand placed, including joint reinforcement & sawcut	\$60.01	\$53.11
10" Commercial Concrete	Square Yard	Slip formed, including joint reinforcement & sawcut	\$57.01	\$50.45
4" CSB for Commercial Concrete	Square Yard	CSB for commercial concrete street	\$7.62	\$6.74
1.5" Surface Asphalt	Square Yard		\$9.66	\$8.55
1.25" Surface Asphalt	Square Yard		\$8.32	\$7.36
24" Concrete Curb	Lineal Foot	Hand formed and placed	\$27.00	\$23.90
24" Concrete Curb	Lineal Foot	Straight slip formed.(+ 10' of hand placed curb per Catch Basin)	\$9.70	\$8.58
24" Concrete Curb	Lineal Foot	Radius slip formed. (intersections and cul-de-sacs)	\$12.40	\$10.97
10.5" Base Asphalt	Square Yard	Base asphalt full depth Res. Collector	\$53.18	\$47.06
8.75" Base Asphalt	Square Yard	Base asphalt full depth Res. Subcollector	\$44.85	\$39.69
8" Base Asphalt	Square Yard	Base asphalt full depth Res. Local	\$39.70	\$35.13
7.75" Base Asphalt	Square Yard	Base asphalt (for placement over CSB Res. Collector)	\$38.52	\$34.09
6" Base Asphalt	Square Yard	Base asphalt (for placement over CSB Res. Subcollector)	\$30.17	\$26.70
5" Base Asphalt	Square Yard	Base asphalt (for placement over CSB Res. Local)	\$25.40	\$22.48
5.75" Base Asphalt	Square Yard	Base asphalt (for placement over CSB & Geogrid Res. Collector)	\$28.97	\$25.64
4" Base Asphalt	Square Yard	Base asphalt (for placement over CSB & Geogrid Res. Subcollector)	\$19.07	\$16.88
3" Base Asphalt	Square Yard	Base asphalt (for placement over CSB & Geogrid Res. Local)	\$14.30	\$12.66
7" Crushed Stone Base (CSB)	Square Yard	Base for asphalt with or without geogrid	\$12.67	\$11.21
14" Commercial Base Asphalt	Square Yard	Base asphalt (for placement over CSB Commercial)	\$69.87	\$61.83
12" Commercial Base Asphalt	Square Yard	Base asphalt (for placement over CSB & Geogrid Commercial)	\$60.34	\$53.40
Geogrid (Tensar TX5)	Square Yard	Optional for asphalt pavements	\$0.99	\$0.88
Edge Drain	Square Yard	Per Square Yard of Street	\$1.42	\$1.26
Edge Drain	Lineal Foot	Per Lineal Foot of Curb	\$1.98	\$1.75
Milling	Square Yard	1" to 3" deep	\$3.55	\$3.14
Joint Sealant (Curb & Gutter)	Lineal Foot	Curb & Gutter. Calculate by LF of curb	\$4.30	\$3.81
Joint Sealant (Full Width Street)	Lineal Foot	Full width street. Calculate by LF of street centerline	\$9.46	\$8.37
Sidewalk, Concrete	Lineal Foot	4' wide 4" thick	\$25.35	\$22.43
Sidewalk, Concrete	Lineal Foot	5' wide 4" thick	\$30.75	\$27.21
Sidewalk, Asphalt	Lineal Foot	5' wide 5" thick.	\$23.69	\$20.97
8' Wide Multi Use Path	Lineal Foot	8' wide 5" thick	\$37.91	\$33.55
10' Wide Multi Use Path	Lineal Foot	10' wide 5" thick	\$47.39	\$41.94
12' Wide Multi Use Path	Lineal Foot	12' wide 5" thick	\$56.87	\$50.33
Seed & Mulch	Square Yard	Under 1 acre to cover.	\$2.28	\$2.02
Seed & Mulch	Square Yard	Over 1 acre to cover.	\$0.93	\$0.82
ADA Curb Ramp	Each	Not derived from Means Book.	\$1,400.00	\$1,400.00
Subgrade Prep	Square Yard	Grading, compaction & water conditioning	\$1.67	\$1.48
Trench Excavation		Engineers estimate required.		
Bulk Excavation		Engineers estimate required.		