

RS Means Cost Data				
Item	Unit	Notes:	2019 Cost	2019 Cost Index (0.881)
7" Residential Concrete	Square Yard	Hand formed & placed	\$38.00	\$33.48
8" Residential Concrete	Square Yard	Hand formed & placed	\$42.50	\$37.44
9" Residential Concrete	Square Yard	Hand formed & placed	\$48.50	\$42.73
7" Residential Concrete	Square Yard	Slip formed	\$35.00	\$30.84
8" Residential Concrete	Square Yard	Slip formed	\$39.50	\$34.80
9" Residential Concrete	Square Yard	Slip formed	\$45.00	\$39.65
10" Commercial Concrete	Square Yard	Hand placed, including joint reinforcement & sawcut	\$61.02	\$53.76
10" Commercial Concrete	Square Yard	Slip formed, including joint reinforcement & sawcut	\$58.02	\$51.12
4" CSB for Commercial Concrete	Square Yard	CSB for commercial concrete street	\$10.64	\$9.37
1.5" Surface Asphalt	Square Yard		\$9.66	\$8.51
1.25" Surface Asphalt	Square Yard		\$8.32	\$7.33
24" Concrete Curb	Lineal Foot	Hand formed and placed	\$28.00	\$24.67
24" Concrete Curb	Lineal Foot	Straight slip formed.(+ 10' of hand placed curb per Catch Basin)	\$9.90	\$8.72
24" Concrete Curb	Lineal Foot	Radius slip formed. (intersections and cul-de-sacs)	\$12.65	\$11.14
10.5" Base Asphalt	Square Yard	Base asphalt full depth Res. Collector	\$52.79	\$46.51
8.75" Base Asphalt	Square Yard	Base asphalt full depth Res. Subcollector	\$44.52	\$39.22
8" Base Asphalt	Square Yard	Base asphalt full depth Res. Local	\$39.38	\$34.69
7.75" Base Asphalt	Square Yard	Base asphalt (for placement over CSB Res. Collector)	\$38.20	\$33.65
6" Base Asphalt	Square Yard	Base asphalt (for placement over CSB Res. Subcollector)	\$29.93	\$26.37
5" Base Asphalt	Square Yard	Base asphalt (for placement over CSB Res. Local)	\$25.21	\$22.21
5.75" Base Asphalt	Square Yard	Base asphalt (for placement over CSB & Geogrid Res. Collector)	\$28.75	\$25.33
4" Base Asphalt	Square Yard	Base asphalt (for placement over CSB & Geogrid Res. Subcollector)	\$18.89	\$16.64
3" Base Asphalt	Square Yard	Base asphalt (for placement over CSB & Geogrid Res. Local)	\$14.17	\$12.48
7" Crushed Stone Base (CSB)	Square Yard	Base for asphalt with or without geogrid	\$17.89	\$15.76
14" Commercial Base Asphalt	Square Yard	Base asphalt (for placement over CSB Commercial)	\$69.31	\$61.06
12" Commercial Base Asphalt	Square Yard	Base asphalt (for placement over CSB & Geogrid Commercial)	\$59.87	\$52.75
Geogrid (Tensar TX5)	Square Yard	Optional for asphalt pavements	\$1.04	\$0.92
Edge Drain	Square Yard	Per Square Yard of Street	\$1.40	\$1.23
Edge Drain	Lineal Foot	Per Lineal Foot of Curb	\$1.94	\$1.71
Milling	Square Yard	1" to 3" deep	\$3.59	\$3.16
Joint Sealant (Curb & Gutter)	Lineal Foot	Curb & Gutter. Calculate by LF of street centerline	\$8.73	\$7.69
Joint Sealant (Full Width Street)	Lineal Foot	Full width street. Calculate by LF of street centerline	\$10.47	\$9.22
Sidewalk, Concrete	Lineal Foot	4' wide 4" thick	\$26.50	\$23.35
Sidewalk, Concrete	Lineal Foot	5' wide 4" thick	\$32.25	\$28.41
Sidewalk, Asphalt	Lineal Foot	5' wide 5" thick.	\$23.74	\$20.91
8' Wide Multi Use Path	Lineal Foot	8' wide 5" thick	\$37.98	\$33.46
10' Wide Multi Use Path	Lineal Foot	10' wide 5" thick	\$47.48	\$41.83
12' Wide Multi Use Path	Lineal Foot	12' wide 5" thick	\$56.97	\$50.19
Seed & Mulch	Square Yard	Under 1 acre to cover.	\$2.35	\$2.07
Seed & Mulch	Square Yard	Over 1 acre to cover.	\$0.96	\$0.85
ADA Curb Ramp	Each	Not derived from Means Book.	\$1,400.00	\$1,400.00
Subgrade Prep	Square Yard	Grading, compaction & water conditioning	\$1.71	\$1.51
Trench Excavation		Engineers estimate required.	\$0.00	
Bulk Excavation		Engineers estimate required.	\$0.00	